


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Affidavit Required  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Pawnee County, Sec. 5 Twp. 21 Rge. 15 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW NW SE  
Lease Owner Fender Pipe & Supply, Inc.  
Lease Name Bowman Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 2-4-65 19\_\_\_\_  
Plugging completed 2-6-65 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3868 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	946'	None
				5-1/2"	3866'	3069'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3868', sanded hole to 3742' and dumped 4 sacks of cement @ 3742' with dumpbailer. Pulled 5 1/2" casing to 916' and circulated with 22 sacks of gel mud. Pulled 5 1/2" casing to 360' and pumped 25 sacks of cement. Pulled 5 1/2" casing to 160' and pumped 25 sacks of cement. Pulled balance of 5 1/2" casing, bailed hole to 30' and ran 10 sacks of cement to base of cellar.

2-17-68

RECEIVED  
STATE CORPORATION COMMISSION

FEB 17 1968

PLUGGING COMPLETE.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of February, 1965

My commission expires May 20, 1968  
Milton J. Volin Notary Public.