

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

5
Pawnee County. Sec. 8 Twp. 21 Rge. 15 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines ~~SE/SE/NE~~ SE SW NW
Lease Owner Petroleum Management Inc.
Lease Name Rosebush Well No. 1
Office Address 1515 Wichita Plaza Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Mar 4 19 64
Application for plugging filed Apr 2 19 64
Application for plugging approved Around Apr 6 19 64
Plugging commenced Apr. 8, 19 64
Plugging completed Apr. 11, 19 64
Reason for abandonment of well or producing formation No longer a producer.

NORTH

			#

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production Feb 28 1964
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3865 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	971'	None
				5 1/2	3865'	2010'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 3815' to 3760'. Mixed and dumped
5 sx. of cement from 3760' to 3728'. Pulled casing.
Mixed and pumped in 40 sx. of gel mud. Put in plug. Mixed and
pumped in 100 sx. of cement from 300' to base of the cellar.
1,000 lbs pumping pressure maximum.

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 1964
5-6-64

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.
Address Box 304 Great Bend, Ks.

STATE OF Kansas, COUNTY OF Barton, ss.
William D. Hoberecht (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Russell D. Hoberecht
Box 304 Great Bend, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 1964

My commission expires March, 1966

Shirley V. Mauer
Notary Public.


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company: SIERRA PETROLEUM CO., INC.
Farm: Rosebush No. 1

SEC. 5 T. 21 R. 15W
SE 34/4 SW

Total Depth. 3842'
Comm. 8-31-56 Comp. 9-14-56
Shot or Treated.
Contractor.
Issued. 10-20-56

County Payne
KANSAS



Elevation. 1961' KB

Production. 5,445,000 CF/GPD

CASING:

8 5/8" @962' w/425 sx cem.
5 1/2" @3840 1/2' w/125 sx cem.

Figures indicate Bottom of Formations

surface clay sand & shale	100
red bed & shale	340
sand & shale	498
red bed & shale	950
anhydrite	976
shale & shells	1450
shale & salt	1740
shale, lime & shells	1780
shale & lime	2045
lime	2070
lime & shale	2110
lime	2350
shale & lime	3115
lime	3325
lime & shale	3415
lime	3691
lime & shale	3795
Arbuckle	3842
Total Depth	

TOPS:

Anhydrite	950
Hoebner	3312
Brown Line	3409
Lansing Kansas City	3419
Conglomerate	3695
Simpson	3736
Arbuckle	3768

RECEIVED
STATE CORPORATION COMMISSION

MAY 8 1964

CONSERVATION DIVISION
Wichita, Kansas