


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Lawnee County. Sec 8 Twp. 21 Rge. 15 (E) (W)#  
Location as "NE/CNW/SW" or footage from lines NW NW Sw  
Lease Owner Messman & Rinehart Oil Co.  
Lease Name Sweeney Well No. I  
Office Address 1432 Wichita Plaza Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed Oct 1965  
Application for plugging approved Oct 1965  
Plugging commenced Oct 28 1965  
Plugging completed Nov I 1965  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Liker  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3841' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,238'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom of hole with rock. Rock from 3,838' to 3,800'. Dumped 4 sx cement. Mudded hole to 490'. Made 10' of rock bridge. Dumped 20 sx of cement. Mudded hole to 210'. Made 10' of rock bridge. Dumped 20 sx of cement. Mudded hole to 35'. Made 5' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar/

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 8 1965  
11-8-65  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
2809 King St. Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this I day of November, 19 65

My commission expires January 5, 1966

[Signature]  
Notary Public.

NO. 1 SWEENEY "A"

Well Record

Location: NW NW SW, 8-21S-15W  
Pawnee County, Kansas

Commenced: October 11, 1954

Operator: Graham-Messman-Rinehart Drilling Co.  
1005 East Second, Wichita, Kansas

Completed: October 22, 1954

Elevation: 1961 KB

Contractor: Graham-Messman-Rinehart Oil Co.  
1005 East Second, Wichita, Kansas

Production:

Casing Record: 8 5/8" @ 952' w/400 sacks cement  
5 1/2" @ 3841' w/75 sacks cement

.....L O G.....

Sand-shale	85
Shale-dolomite-sandstone	366
Dakota sand	482
Shale	952
Anhydrite	965
Shale	1900
Fort Riley lime	2093
Lime	2215
Shale-Lime	2365
Lime-shale	2990
Shale-lime	3340
Lime-shale	3490
Lime	3693
Lime-chert	3751
Lime-shale	3800
Arbuckle	3841 R.T.D.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 10 1965

CONSERVATION DIVISION  
Wichita, Kansas

Anhydrite	937 (+1024)
Heebner	3324 (1363)
Brown Lime	3421 (-1460)
Lansing	3432 (-1471)
Conglomerate	3692 (-1731)
Viola	3720 (-1759)
Simpson	3756 (-1795)
Arbuckle	3791 (-1830)

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART OIL COMPANY


By: J. A. Gilliland  
J. A. Gilliland

Subscribed and sworn to before me this  
26th day of October 1954.

Barbara J. Scott  
Notary Public

My Commission Expires: December 1, 1956

GMR  
File Copy



Copies to N.G. - Kans. Geol. S.

NO. 1 SWEENEY "A"

NW NW SW, 8-21S-15W  
Pawnee County, Kansas

## SUPPLEMENTAL REPORT OF CABLE TOOL UNIT ACTIVITY:

Moved in cable tools November 1, 1954.

Drilled deeper to 3843'. Ran log. Bailed 5 GO and 2 GW  
per hour for four hours, from 3841-43'.

Set Baker plug at 3836'. Perf 3823-33' w/40<sup>s</sup>.

Completed at 5 million cfg per day natural.

GMR  
File Copy

copy to ALB