


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

21 15

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 7 Twp. 15 Rge. 21 ~~W~~ W (W)
Location as "NE/CNW/SW" or footage from lines 500' S of N Line - 500' W of E
Lease Owner Kansas-Nebraska Natl. Gas Co., Inc. NE/4
Lease Name Spreier Well No. 1
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 1 19 55
Application for plugging filed January 1 19 55
Application for plugging approved January 1 19 55
Plugging commenced 6:00 P.M. January 1 19 55
Plugging completed 8:30 P.M. January 1 19 55
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Phone - Warren Horner

Name of Conservation Agent who supervised plugging of this well Warren Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3890' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Anhydrite</u>				<u>8-5/8"</u>	<u>959'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 300'. 1/3 sacks hulls and plug
XXXX cemented at 300' with 20 sacks hand mixed cement through drill
pipe.

Filled hole with heavy rotary mud to 35'. 1/3 sack hulls and plug cemented
at 35' with 20 sacks hand mixed cement through drill pipe. Cement
to bottom of cellar.

1-8-55

STATE CORPORATION COMMISSION
WICHITA, KANSAS

JAN 8 - 1955

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Honaker Drlg., Inc.
Address 2008 Lakin, Great Bend, Kansas

STATE OF _____, COUNTY OF _____, ss. _____
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2008 Lakin, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of January, 19 55
[Signature] Notary Public.

My commission expires June 25, 1955

PLUGGING
FILE SEC 7 TWP 15 RGE 21
BOOK PAGE 89 LINE 19

HONAKER DRILLING, INC.
2008 LAKIN
GREAT BEND, KANSAS

DRILLERS' LOG

Spreier Well No. 1	Comm: 12-19-54
Loc: 500' S of N. Line	Comp: 1-1-55
500' W of E Line NE/4	Elevation: 1962 D.F.
Sec: 7-21S-15W	Total Depth: 3890'
Pawnee County, Kansas	Casing: 8-5/8" @ 959'
Company: Kansas-Nebraska Natural Gas Co., Inc.	

0	80	Sand & Gravel.	
80	375	Blue Shale.	
375	485	Dakota Sand.	
485	949	Red Bed & Shale.	
949	980	Anhydrite.	8-5/8" casing cemented
980	1485	Shale & Shells.	@ 959' with 500 sacks
1485	1585	Salt & Shale.	Poz. Mix and 8 sacks
1585	1760	Shale & Shells.	XXXX calcium chloride.
1760	3546	Lime & Shale.	
3546	3890	Lime.	
3890		Total Rotary Depth.	D & A.

I certify that this is the true and correct copy of the above log, to the best of my knowledge.

[Handwritten Signature]

Subscribed and sworn to before me this 6th day of January, 1955.

[Handwritten Signature]
Notary Public

My Commission Expires: 6-15-55

DRILLING
FILE SEC 7-21-15W
BOOK PAGE 89 LINE 19