


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Pawnee County, Sec. 7 Twp. 21 Rge. 15 (E) (W)  
Location as "NE/CNWKSW" or footage from lines NE - NE - SE  
Lease Owner Great Bend Pipe and Supply Co.  
Lease Name Ennefer Well No. 1  
Office Address Drawer "B", Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19\_\_  
Application for plugging filed 19\_\_  
Application for plugging approved 19\_\_  
Plugging commenced 5-13 19 61  
Plugging completed 5-17 19 61  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot.  
Producing formation Depth to top Bottom Total Depth of Well 3863' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	953	None
				5 1/2"	3862	3118'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 3850' - dumped 5 sks cement - pulled casing - mudded hole to 300' - set 10' rock bridge - dumped 25 sks cement - mudded hole to 35' - set 10' rock bridge - dumped 10 sks cement

RECEIVED  
STATE CORPORATION COMMISSION

JUN 5 1961

CONSERVATION DIVISION  
Wichita, Kansas

6-5-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D casing Pulling Co. License # 236  
Address Box 572, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Nathan Meltzer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nathan Meltzer

(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June 19 61

Anne Meltzer Notary Public.

My commission expires MY COMMISSION EXPIRES MARCH 30, 1965



Great Bend No 5. Co.

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
503 East Murdock,  
Wichita, KansasCompany: HONAKER DRILLING, INC., et al  
Farm: Ennefer No. 1SEC. 7 T. 21 R. 15W  
NE NE SETotal Depth. 3863  
Comm. 9-21-55 Comp. 10-2-55  
Shot or Tested.  
Contractor: Honaker Drilling, Inc.  
Issued. 11-19-55County Pawnee  
KANSASCASING:  
8 5/8 @ 953' w/ 200 sx cmt.  
5 1/2 @ 3862' w/ 125 sx cmt.

Elevation. 1960 DF

Production. 2,380,000 CFGPD

Figures indicate Bottom of formation.

top soil & sand	20
sand & gravel	210
shale	360
Dakota sand	435
red bed	560
red bed & shale	943
anhydrite	990
shale & shells	1490
salt & shale	1590
shale & shells	1780
lime & shale	3469
lime	3710
lime & chert	3745
lime	3757
lime & shale	3819
lime	3863
Total Depth	

## TOPS:

Heebner	3334
Brown lime	3429
Lansing-KC	3439
Cherty conglomerate	3696
Simpson	3753
Arbuckle	3793

DST #1: 3717-45, open 30 min. SI 30  
min; wk. blw 7 and 4 min. rec. 63'  
mud, BHP OffDST #2: 3794-3819, open 30 min. SI  
20 min. blow: 4,620 MCFG, rec. GCM,  
Press. not recorded.

RECEIVED  
STATE DEPARTMENT OF REVENUE,  
MISSOURI

MAY 2 1961

CONSERVATION DIVISION  
Wichita, Kansas