


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County. Sec. 7 Twp. 21 Rge. (E) 15 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NE  
Lease Owner Santa Fe Pipe & Supply Co.  
Lease Name Spreier Well No. 2  
Office Address Box 562, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 2-4 \_\_\_\_\_ 19 63  
Plugging completed 2-9 \_\_\_\_\_ 19 63  
Reason for abandonment of well or producing formation depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3822 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	949	8 5/8"	949	none
		0	3822	5 1/2"	3822	1897.15

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed plug to 3750', set 10' rock bridge, and dumped 4  
sacks of cement at 3740'. Load hole with mud. Pumped in  
25 sacks of cement at 350'. Mudded back to 180'. Pumped  
in 25 sacks of cement at 180'. Capped hole with 10 sacks  
of cement.

FEB 27 1963

2-27-63

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pullers, Inc.  
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Dean Wells (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells  
Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of February, 19 63

My commission expires July 7, 1964

[Signature] Notary Public.

15-145-01364-0000  
 WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas


KANSAS-NEBRASKA NATURAL GAS CO. &  
 Company GULF OIL CORPORATION  
 Farm Sprier No. 2

SEC. 7 T. 21 R. 15W  
 SE SE NE

Total Depth. 3823  
 Comm. 4-26-55  
 Shot or Treated.  
 Contractor.  
 Issued. 7-23-55

Comp. 5-9-55

County Pawnee  
 KANSAS



Elevation. 1962 RB

Production. 2,500,000 CFG

CASING:

8 5/8 @ 949' w/ 500 cu' cmt.  
 5 1/2 @ 3822' w/ 150 cu' cmt.

Figures indicate Bottom of Formations

sand & gravel	100
red bed & clay	368
Dakota sand	478
shale & shells	530
red bed & shale	940
anhydrite	970
shale & shells	1440
salt & shale	1520
salt & lime	1770
lime	1780
lime & shale	3553
lime	3704
chert & shale	3747
chert & lime	3750
shale & lime	3792
core	3823
Total Depth	

SCOUT TOPS:

Heebner	3317
Brown, lime	3414
Lansing	3424
Conglomerate	3678
Viola	3704
Simpson	3738
Arbuckle	3781

WELL LOG BUREAU  
 STATE CORPORATION

FEB 27 1963

CONSERVATION DIV.  
 Wichita, Kansas