STATE CORPORATION COMMISSION CONSERVATION DIVISION 200 Colorado Derby Building Wichita, Kansas 67202


15.083-21184-0000

15-083-21184(PLEASE TYPE FORM and File ONE COPY)

API # / 26/85 (Identifier number of this well). This must be listed for wells driftled since 1967; if no API# was issued, indicate spud or completion date.
WELL OPERATORNEYENNE Oil Service, Inc. (cwner/ccmpany name) (cwner/ccmpany name) (cwner/ccmpany name)
ADDRESS P.O. Box 384 (cwner/company name) (operator's) ADDRESS P.O. Box 384
STATE Kansas ZIP CODE 67560 CONTACT PHONE # (913) 798-2282
LEASE Wieland WELL# 1 SEC. 16 T. 21 R. 22 (XXXX/West)
-NW-SE-SW SPOT LOCATION/COCO COUNTY Hodgeman
FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)
FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)
Check One: OIL WELL X GAS WELL DGA SWD/ENHR WELL DOCKET#
CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS
SURFACE CASING SIZE 8 5/8 SET AT 471 CEMENTED WITH 275 SACKS
PRODUCTION CASING SIZE $\frac{4\frac{1}{2}}{2}$ SET AT $\frac{4520}{4520}$ CEMENTED WITH $\frac{110}{2}$ SACKS
LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 2283/2289 T.D. 4520 PBTD ANHYDRITE DEPTH (Stone Corral Formation)
CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE
PROPOSED METHOD OF PLUGGING Ask Richard Lacey 1-13-97 W
· <u>'U 179</u>
(If additional space is needed attach separate page)
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED?
If not explain why?
PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seg. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.
LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Paul L. Cambron PHONE# (91% 798-2282 .
ADDRESS P.O. Box 384 City/State Ness City, KS 67560
PLUGGING CONTRACTOR Cheyenne Well Service, Inc. KCC LICENSE # 06454 99
PLUGGING CONTRACTOR Cheyenne Well Service, Inc. KCC LICENSE # 06454 6/9 (company name) (contractor's) ADDRESS P.O. Box 384 Ness City, KS 67560 PHONE # (91% 798-2282
PROPOSED DATE AND HOUR OF PLUGGING (If Known?)
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUPERANTEED BY OPERATOR OR AGENT
DATE: 1/10/97 AUTHORIZED OPERATOR/NORMY (Signature)

15-083-21184-0000

SAGE DRILLING COMPANY 202 S. ST. FRANCIS WICHITA, KS 67202 COMPANY TOOLS	#1 WIELAND 16-21-22W #1 WIELAND NW SE SW HODGEMAN FIELD WIELAND ++++ # 4/18/85 ** P 25.92 80 & 8 8/85 BWPD MISS 4397-4408 OA	
HEEB 3744-1455 LANS 3794-1505 FT SC 4212-1923 CHER 4340-2051 MISS 4392-2103 RID<D 4520-2231	API 15-083-2I, 184 8 5/8 - 471 / 2755X, 4 1/2 - 4520 / 1105X OST (1) 4320-50 (FT SC, CHER) / 30-60-60-120, 280' GIP, REC 80' 50 & GCM (5% OIL, 3% G, 92% M), SIP 193-308#, FP 89-58 / 120-67#, HP 2100-2046#, 8HT 109' OST (2) 4394-4420 (MISS) / 30-60-60-120, REC 600' FREE OIL (GR 35°), 300' G & 0CM (30% G, 35% OIL, 25% M, 10% W), 60' GSY OILY M (25% G, 35% OIL, 20% M, 20% W), 120' O & MCW (10% OIL, 20% M, 70% W), SIP 1334-1336#, FP 157-265 / 376-473#, HP 2120-2102#, BHT 121' OST (3) 4420-30 (MISS) / 30-60-60-120, REC 20' FREE OIL, 940' WIR, SIP 1369-1378#, FP 89-265 / 328-452#, HP 2145-2090#, BHT 131' DST (4) 4430-45 (MISS) / 30-60-60-120, REC 2730' WTR, SIP 1375-1385#, FP 132-717 / 848-1111#, BHT 137°	, T
CUPYRIGHT 1984 BEDEPENDENT OIL & GAS SERVICE, INC. WICHTA, MANEAS	MICT - CO. SOZ'O W / 48SX AT 4417', CO CMT. PF (MISS) 4404- 08. W / 4 SPF, SWB DWN. NAT, SO, PF (MISS) 4397-99. W / 4 SPF, SWB DWN. NAT, SO, SET 2 3/8 " TBG AT 4430', POP, P 26.92 BG & 8 BWPD, 2/27/85	.: .:





Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 13, 1997

Cheyenne Oil Service Inc P O Box 384 Ness City KS 67560 Wieland #1
API 15-083-21,184-0000
NW SE SW
Sec. 16-21S-22W
Hodgeman County

Dear Paul L. Cambron,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Production Supervisor

Production supervise

District: #1 304 W. McArtor Dodge City, KS 67801 (316) 225-6760