

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-19092-00-01  
Spot: NWSWNW Sec/Twnshp/Rge: 21-19S-10W  
3625 feet from S Section Line, 4973 feet from E Section Line  
Lease Name: EATINGER Well #: 2  
County: RICE Total Vertical Depth: 3207 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2700		
CIBP	5.5	2900		
PROD	5.5	3179		125 SX
SURF	10.75	152		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/21/2017 9:30 AM  
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.  
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/21/2017 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU TUBING STUCK IN HOLE & SHOT OFF AT 2957'. SET CIBP AT 2900' AND CAP WITH 2 SX'S CEMENT. SET CIBP AT 2700' AND CAP WITH 2 SX'S CEMENT. PERFORATE AT 1250', 900', AND 250'. RUN TUBING TO 1250' AND PUMP 35 SX'S COMMON CEMENT WITH 2% CC, PULL TUBING TO 900' AND WAIT AWHILE. TAG CEMENT AT 1000'. PUMP 35 SX'S COMMON WITH 2% CC AT 900'. PULL TUBING TO 250'. TAG CEMENT AT 870'. PUMPED 95 SX'S AND GOT CEMENT CIRCULATION TO SURFACE FROM 250'. PULLED TUBING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
2986	2989	CSG	
2744	2751	CSG	

INVOICED  
MAY 22 2017

Remarks: EXCEL TICKET #1448 FOR SETTING CIBP'S. EXCEL TICKET #1269 FOR PERFORATING. SWIFT SERVICES CEMENT # 30000.

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)