

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-21003-00-00
Spot: SWSENWSW Sec/Twnshp/Rge: 30-30S-41W
1400 feet from S Section Line, 4573 feet from E Section Line
Lease Name: REED-BRAMLETT Well #: 2-30
County: STANTON Total Vertical Depth: 5630 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1590		
CIBP		5080		WITH 2 SX CMT
PROD	4.5	5315	0	WITH 150 SX CMT
SURF	8.625	1524		WITH 505 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/13/2017 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY Phone: (620) 793-8186

Proposed Plugging Method: SET CIBP @ 5080' WITH 2 SX CMT. CASING LEAKS AT 3917'-45' (TIGHT & CANNOT PUMP IN TO) AND 1652'-85' (OPEN & CAN PUMP IN TO). PLUG AT 1650' WITH 80 SX CMT INTO CASING LEAKS. PERFORATE AT 550' & CIRCULATE CMT TO 0'.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2017 4:45 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5080' WITH 2 SX CMT. 1ST PLUG AT 1653' WITH 80 SX CMT & 250# HULLS. WAIT ON CMT. NO TAG. SET CIBP @ 1590' & TEST CASING TO 600 PSI. HOLDING. PERFORATE AT 1560' WITH 50 SX CMT & 150# HULLS. 2ND PLUG PERFORATE AT 550' & PUMP 235 SX CMT. CIRCULATED TO 0'.

Perfs:

Top	Bot	Thru	Comments
5130	5170		

INVOICED
MAY 22 2017

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed _____

Kenny Sullivan
SA (TECHNICIAN)

RECEIVED
APR 18 2017
KCC DODGE CITY