

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-20525-00-00
Spot: NWNWSESW Sec/Twnship/Rge: 17-27S-40W
1265 feet from S Section Line, 3900 feet from E Section Line
Lease Name: CARRITHERS Well #: 2
County: STANTON Total Vertical Depth: 2700 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2542	0	WITH 395 SX CMT
SURF	8.625	736		WITH 350 SX CMT

Well Type: GAS UTC Docket No: _____ Date/Time to Plug: 04/24/2017 9:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: TIM JULIAN Company: ABERCROMBIE ENERGY Phone: (620) 793-8186

Proposed Plugging Method:

PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.
--

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/24/2017 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 250# HULLS & 185 SX CMT DOWN 5 1/2" CASING TO 2424'. DISPLACE TO 675' WITH WATER. PERFORATE 4 HOLES AT 370'. ATTEMPT TO PUMP INTO PERFS. PUMPING 1 BPM AT 700#. NO BLOW OUT 8 5/8" CASING. PUMP 45 SX CMT WITH 50# HULLS TO 500' DOWN THE 5 1/2" CASING. STANDING PRESSURE OF 600#. CLOSE WELL IN. PUMP 15 SX CMT DOWN THE ANNULUS TO 200#.

Perfs:

Top	Bot	Thru	Comments
2414	2424		
2230	2239		


INVOICED
MAY 22 2017

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
MAY - 2 2017
KCC DODGE CITY