

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-20992-00-00
Spot: N2SESENW Sec/Twnshp/Rge: 30-30S-41W
3033 feet from S Section Line, 2954 feet from E Section Line
Lease Name: REED-BRAMLETT Well #: 1-30
County: STANTON Total Vertical Depth: 5600 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 1658 | | |
| CIBP | | 2974 | | WITH 2 SX CMT |
| DVT | | 3013 | | WITH 165 SX CMT |
| PROD | 5.5 | 5313 | | WITH 125 SX CMT |
| SURF | 8.625 | 1518 | | WITH 485 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/21/2017 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: TIM JULIAN Company: ABERCROMBIE ENERGY Phone: (620) 793-8186

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2017 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG STUCK AT 3004' (FREE POINT) DUE TO A CASING LEAK. CUT TBG AT 2984'.
SET CIBP @ 2974' WITH 2 SX CMT. CASING WOULD NOT TEST ABOVE THE CIBP.
SET CIBP @ 1658'. TEST CASING TO 350#. HOLDING. PERFORATE AT 1648'.
CIRCULATE CMT FROM 1648' TO 0' USING 390 SX CMT LEAVING THE 5 1/2"
CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 5133 | 5160 | | |


INVOICED
MAY 22 2017

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
APR 27 2017
KCC DODGE CITY