

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-19030-00-00
Spot: S2NENE Sec/Twnshp/Rge: 12-31S-9W
4290 feet from S Section Line, 660 feet from E Section Line
Lease Name: MUIR LEASE NCRA Well #: 2
County: HARPER Total Vertical Depth: 4490 feet

Operator License No.: 34318

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4489		125 SX
SURF	8.625	172		100 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/25/2017 8:00 AM

Plug Co. License No.: 34879

Plug Co. Name: CANAAN WELL SERVICE INC.

Proposal Revd. from: CHARLES MILLER

Company: BEREXCO

Phone: (316) 215-2797

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 04/25/2017 5:00 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

CIBP AT 4361' WITH 2 SXS CEMENT. RUN TUBING TO 3000' & FILLED WITH MUD. SHOT 1514' NO RECOVERY. PERF'D AT 1514' & SPOTTED 50 SX CEMENT. TAGGED CEMENT AT 1250'. RUN IN HOLE TO SHOT PIPE AT 950'. BRIDGE AT 930', PERF'D PIPE AT 930' PUMPED 50 SX CEMENT THRU TUBING. PERF'D 4 HOLES AT 300'. RAN TUBING TO 300' & CIRCULATED CEMENT TO SURFACE.


Top	Bot	Thru	Comments
4423	4434		

Remarks: COMPLIANCE DENIED TA

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED
MAY 22 2017

JK