

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-26661-00-00
Spot: NESWNENW Sec/Twnshp/Rge: 25-34S-9E
4505 feet from S Section Line, 3349 feet from E Section Line
Lease Name: HOUSE Well #: 3-25
County: CHAUTAUQUA Total Vertical Depth: 2485 feet

Operator License No.: 35018
Op Name: ENTRANSCO ENERGY, LLC
Address: PO BOX 578
DEWEY, OK 74029

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2477		420 SX
SURF	8.625	55		35 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: RAY GILBERT Company: _____ Phone: (620) 820-9687

Proposed
Plugging
Method:

Plug per KCC regulations

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/26/2017 3:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1700' gelled hole and spotted 10 sack plug. Pulled up to 1000' and spotted 5 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 70 sacks of cement were used to plug this well. Well was cut off.

Perfs:


Top	Bot	Thru	Comments
2068	2082		
RECEIVED KCC DIST # 3 MAY 02 2017 CHANUTE, KS DS			

Remarks: WELL WAS ON COMPLIANCE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 15 2017
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

INVOICED
MAY 22 2017