

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-20198-00-02
Spot: NENENW Sec/Twnshp/Rge: 2-34S-2E
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: CASTER Well #: 2-3
County: SUMNER Total Vertical Depth: 2766 feet

Operator License No.: 32984
Op Name: GOBY ENERGY, INC.
Address: 51000 TWO RIVERS PLAZA
GLENWOOD SPRINGS, CO 81601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2766		100 SX
SURF	8.625	250		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/26/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-6964

Proposed Plugging Method: SET CIBP ABOVE PERFS & CAP W/ 2 SX. SHOOT OFF 4 1/2" CASING, PULL TO 300' & CIRCULATE TO SURFACE.

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE
Date/Time Plugging Completed: 04/26/2017 5:30 PM KCC Agent: JEFF KLOCK

Actual Plugging Report:

SET CIBP @ 2660' & CAP W/ 2 SX. SHOT CASING OFF AT 900' AND PULLED TO 350'. CIRCULATED CEMENT TO SURFACE WITH 130 SX 60/40 4%. PULLED THE REST OF CASING & TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
2712	2722		

Remarks: QWS TICKET #6657

Plugged through: CSG

INVOICED
MAY 22 2017

District: 02

Signed Jeff Klock DISTRICT SUPERVISOR
(TECHNICIAN)