

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21500-00-00
Spot: NENESWSW Sec/Twship/Rge: 1-31S-33W
1250 feet from S Section Line, 4030 feet from E Section Line
Lease Name: STAPLETON Well #: 2
County: SEWARD Total Vertical Depth: 2755 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2751	0	WITH 1075 SX CMT
SURF	8.625	592		WITH 375 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/20/2017 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2017 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG STUCK. CUT TBG AT 1700'. PULL TO 1670' & CIRCULATE CMT TO SURFACE USING 130 SX CMT & 200# HULLS. TOOH WITH TBG. WOC. TOP OFF 4 1/2" WITH 40 SX CMT. PUMP 35 SX CMT DOWN THE ANNULUS. PRESSURE TO 300#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2643	2702		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

INVOICED
MAY 22 2017

District: 01

Signed *Ken Jehlik*
(TECHNICIAN)

RECEIVED
MAY - 2 2017
KCC DODGE CITY