



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1972

CONSERVATION DIVISION
Wichita, Kansas

10-27-72

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Nossaman of Mack Oil Co. has this

date requested permission to plug the following described well:

Mr. Nossaman guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Co.

Complete Address: 812 Union Center, Wichita, Kansas

Lease Name: Ewy Well No. 1

Location: C SE NE Sec. 2 Twp. 21 Rge. 22 ~~(E)~~ (W)

County: Hodgeman Total Depth 4320' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Nossaman was instructed to plug the well as follows:

8 5/8" to 255' circulated w/ cement. Mud 4320' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 250'

Spot 30 sacks cement 250' to 150' Mud 150' to 40'

Plug, Halls & 15 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Eric
Conservation Division Agent