



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 4 1974

CONSERVATION DIVISION  
Wichita, Kansas

9-4-74

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sullivan of Pickrell has this

date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th Nat'l Bk. Bldg., Wichita, Kansas

Lease Name: Cox "A" Well No. 1

Location: C NW SW Sec. 9 Twp. 21 Rge. 22 (E) (W)

County: Hodgeman Total Depth 4506' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sullivan was instructed to plug the well as follows:

8 5/8" to 218' circulated w/ cement. 5 1/2" to 4500' cemented.


Top perforations 4382' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4150' Mud 4150' to 800'

Spot 70 sacks cement 800' to 350' Mud 350' to 300'

Spot 70 sacks cement 300' to 0'.

Very truly yours,

  
Conservation Division Agent