



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 17 1972

CONSERVATION DIVISION
Wichita, Kansas

10-17-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Nossaman of Mack Oil has this

date requested permission to plug the following described well:

Mr. Nossaman guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company

Complete Address: 812 Union Center, Wichita, Kansas

Lease Name: Gus Well No. 1

Location: C SE NW Sec. 15 Twp. 21 Rge. 22 ^{XX}(E)(W)

County: Hodgeman Total Depth 4450' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Nossaman was instructed to plug the well as follows:


8 5/8" to 315' circulated w/ cement. Mud 4450' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 300'

Spot 30 sacks cement 300' to 200' Mud 200' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent