



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1974
8-21-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Parks of O.A. Sutton has this
date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: O.A. Sutton

Complete Address: 800 Sutton Place, Wichita, Kansas

Lease Name: Hamilton Well No. 1

Location: C SW SW Sec. 32 Twp. 21 Rge. 22 (E) (W)

County: Hodgeman Total Depth 4516' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Parks was instructed to plug the well as follows:

8 5/8" to 356' circulated w/ cement. Mud 4516' to 850'

Spot 80 sacks cement 850' to 550' Mud 550' to 356'

Spot 30 sacks cement 356' to 256' Mud 256' to 45'

Plug, H_ulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent