

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 18 TWP. 21s RGE. 22w E/W
Location as in quarters or footage from lines:

C SW NW

Lease Owner Coastal Oil & Gas boughtby Kelso Casing Pulling

Lease Name Cossman #1 Well No. _____

Office Address Box 347, Chase, Kansas, 67524

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 2/16/83

Plugging completed 2/19/83

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Tarbuck

Producing formation _____ Depth to top _____ bottom T.D. 4460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	280'	none
				5 1/2"	4459'	309.03'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded off bottom to 4350' & ran 5 sacks cement. Shot pipe at 3023', 2508', 1999', 515', & 344'. Pulled 10 joints. Plugged well with 1 sack hulls, 15 gal, 70 cement, 20 gal, & 100 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 83



My Commission expires:

STATE CORPORATION COMMISSION
RECEIVED
Notary Public.

MAR 7 1983
CONSERVATION DIVISION
Wichita, Kansas

3-7-83

D R I L L E R S L O G

#1 Cossman

CASING RECORD:
280' of 8-5/8"
surface casing

COMPANY: Colorado Oil and Gas
Corporation
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/SW NW
Section 18-21-22W
Hodgeman County, Kansas

TOTAL DEPTH:
4460'

COMMENCED: July 25, 1960
COMPLETED: August 7, 1960

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	287	Ran 280' of 8-5/8" surface casing; set and cemented at 287.50' with 165 sacks of posmix, 40 cubic feet of strata crete Plug down @ 2:45 A. M. 7-26-1960.
Shale, Shells & Red Bed	287	820	
Anhydrite	820	830	
Shale	830	2150	
Lime & Shale	2150	2550	
Lime	2550	2620	
Lime & Shale	2620	3931	
Lime	3931	4295	
Lime & Shale	4295	4355	
Lime	4355	4388	
Lime & Chert	4388	4460	

Total Depth 4460'

Ran (115 Jts.) of used 5 1/2" casing; set at 4459' 1' off bottom with 100 sacks of posmix. Plug down @ 8:15 A. M. 8-7-1960.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 10th day of August, 1960.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1961

RECEIVED
STATE CORPORATION COMMISSION

JAN 03 1983
CONSERVATION DIVISION
Wichita, Kansas