


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Hodgeman County, Sec. 17 Twp. 21 Rge. 22 (E) W (W)
Location as "NE/CNW&SW" or footage from lines G SE NE
Lease Owner Pickrell Drlg. Co.; Wichita, Kansas 67202
Lease Name Antrim 'A' Well No. # 3
Office Address 705 Fourth National Bank Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed November 1 1961
Application for plugging filed November 23 1970
Application for plugging approved November 24 1970
Plugging commenced November 25 1970
Plugging completed November 30 1970
Reason for abandonment of well or producing formation Depleted
If a producing well is abandoned, date of last production October 31 1970
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eves
Producing formation Mississippian Depth to top 4391 Bottom 4404' Total Depth of Well 4404 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	241	None
				4 1/2"	4384	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

November 25, 1970 Plugged off bottom. Dumped sand to 4350'. Mixed and dumped 4 sx of cement to 4300'.

November 30, 1970 Plugged off top. Globe Oil Well Cementing Co. mixed and pumped down 4 1/2" casing: 7 sx gel, 1 sx hulls, released plug and 35 sx cement. Changed over and mixed and pumped 6 sx gel, 1 sx hulls and 65 sx of cement through braden head, between 4 1/2" and 8 5/8" casings.


RECEIVED
12-14-70
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling, Inc.
Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale M. Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale M. Robinson
705 Fourth National Bank Bldg, Wichita, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 10th day of December, 1970
Esther Lamone
My commission expires January 19, 1973
Notary Public.

File Copy

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita 2, Kansas

LOCATION: ANTRIM A #3 - C SE NE, Sec. 17-21S-22W,
Hodgeman County, Kansas

Rotary Drilling Commenced 9/14/61
Rotary Drilling Completed 9/26/61

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: 241' (5 jts.) 8 5/8" 20# surface casing w/155 sacks cement. Circulated
4399' (139 jts.) 4 1/2" 9.5# Smls. Casing cemented w/100 sacks cement.
Completed 6:30 P. M. 9/25/61.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>Circulated for Samples</u>	
130'	Top Soil, Rock & Clay	4345'	
445'	Blue Shale	4395'	
610'	Shale	4404'	
818'	Shale & Red Bed		
835'	Blaine	<u>Slope Test</u>	
905'	Red Bed & Shale	1815'	0°
1110'	Sand & Shale	2655'	0°
1460'	Red Bed & Shale	3789'	0°
1495'	Anhydrite	4290'	0°
1910'	Shale & Shells		
2460'	Lime & Shale	<u>S. L. M.</u>	
2780'	Lime	1500'	
2825'	Lime & Shale	2500'	
2915'	Lime	3500'	
3590'	Lime & Shale		
3610'	Sand & Lime		
3760'	Lime, Shale & Sand		
3950'	Shale & Lime		
3996'	Lime		
4404'	Lime & Shale R.T.D.		

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1970
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By *C. W. Sebitts*
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 20th day of October, 19 61, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

Maxine Johnson
Maxine Johnson Notary Public

My commission expires: September 24, 1962