


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

15-009-06512-0000  
WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Barton County. Sec. 7 Twp. 16 Rge. (E) 12 (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Graham-Messman-Rinehart Drilling Company  
Lease Name Weber Well No. 1  
Office Address 1005 E. Second St., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 8, 1953  
Application for plugging filed August 8, 1953  
Application for plugging approved August 10, 1953  
Plugging commenced August 8, 1953  
Plugging completed August 8, 1953  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Box 207, Great Bend, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3365 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	310'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom plug at 300 ft. with 1/3 sk. hulls and cemented with 20 sx. cement.  
Top plug at 40 ft. with 1/3 sk. hulls and cemented with 10 sx. cement. Mud to surface.

STATE CORPORATION COMMISSION

REC'D  
08-13-53

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Graham-Messman-Rinehart Oil Company  
Address 1005 E. Second Street, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
J. A. Gilliland (employee of owner) ~~not a conservator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland  
1005 E. Second St., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 53

Barbara J. Scott  
Notary Public.

My commission expires December 1, 1956

24-2675-5 2-52-204

PLUGGING  
FILE SEC 7 T 16 R 12 W  
PAGE 120 LINE 33

WEBER #1

WELL RECORD

Location: NE NE NE, Sec. 7-16-12W  
Barton, County, Kansas

Commenced: July 30, 1953

Completed: August 7, 1953

Operator: Graham-Messman-Rinehart Oil Co.  
1005 E. Second Street  
Wichita, Kansas

Elevation: 1860 K.B.

Production: D & A

Contractor: Graham-Messman-Rinehart Oil Co.

Casing Record: 8 5/8" @ 310' w/200 sx. Cem. & 4 c.c.

LOG

Shale	240
Shale & Sand	310
Sand & Shale	370
Iron Pyrite	405
Red Bed & Shale	865
Shale & Red Bed	1010
Anhydrite	1050
Shale & Shells	1215
Shale & Shells	1530
Shale & Shells	1715
Lime & Shale	1860
Shale & Lime	2000
Shale & Lime	2123
Lime & Shale	2300
Lime & Shale	2510
Lime & Shale	2670
Lime & Shale	2780
Lime & Shale	2865
Lime & Shale	2970
Lime	3040
Lime	3090
Lime	3165
Lime	3210
Lime	3255
Lime & Conglomerate	3340
Arbuckle Lime	3365
T.D.	3365

TOPS:

Heebner	2975	(-1115)
Brown Lime	3040	(-1180)
Lansing-Kr.C.	3056	(-1196)
Conglomerate	3313	(-1453)
Arbuckle	3336	(-1476)
Rotary T. D.	3365	(-1505)

The undersigned, Graham-Messman-Rinehart Oil Company, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

By J. A. Gilliland  
J. A. Gilliland

Subscribed and sworn to before me  
this 12<sup>th</sup> day of August, 1953.

Barbara J. Scott  
Notary Public

My commission expires: Dec. 1, 1956

RECEIVED  
STATE CORPORATION COMMISSION

**PLUGGING**  
FILE SEC 7 T 16 R 12W  
BOOK PAGE 120 LINE 23