


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

15-009-00379-0000  
**WELL PLUGGING RECORD**



Locate well correctly on above Section Plat

Barton County. Sec. 7 Twp. 16 Rge. 12 (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW SW NW  
Lease Owner D. R. Lauck Oil Company Inc. et.al.  
Lease Name Cain Well No. 1  
Office Address 301 S. Broadway Wichita 2 Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed March 11 19 51  
Application for plugging filed March 12 19 51  
Application for plugging approved March 12 19 51  
Plugging commenced March 12 19 51  
Plugging completed March 12 19 51

Reason for abandonment of well or producing formation dry hole  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Stough  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3430 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>Conglomerate</u>	<u>water</u>	<u>3389</u>	<u>3430</u>	<u>10"</u>	<u>242</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud 3433 - 242'  
Bridge 242 - 237  
Cement 237 - 197  
Mud 197 - 30  
Bridge 30 - 26  
Cement 26 - 6 to bottom of cellar

RECEIVED  
MAR 22 1951  
03-22-51  
COMMISSION  
DIVISION

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to D. R. Lauck Oil Company Inc.  
Address 301 S. Broadway Wichita 2 Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
P. R. Bishop (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P. R. Bishop - Pres  
Wichita Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 21 day of March, 19 51  
Elizabeth Kay  
Notary Public

My commission expires Sept. 14, 1951  
28-8278-s 4-50-10M

**PLUGGING**  
FILE SEC 7T-16R12W  
PAGE 67 LINE 9

D. R. LAUCK OIL COMPANY INC. et.al.

Cain #1

Sec. 7 T 16S.R 12W.  
SW SW NW

Barton County Kansas  
Elev.1889 DF

Commenced Mar.1, 1951

Completed Mar.11, 1951

Casing: 10" 242' cemented 165 sacks

Rock & shale	100
shale & shells	142
Shale & shells	370
sand	410
shale & shells	470
sand	490
shale, shells & red bed	805
shale & shells	840
Anhydrite	873
shale, shells & red bed	1040
shale & shells	1105
shale & salt	1250
shale & lime shells	1410
shale & shells	1528
Lime & shale	1595
Lime & shale	1695
Lime & shale	1890
lime	1975
lime & shale	2085
Lime & shale	2225
Lime & shale	2310
lime & shale	2410
lime & shale	2550
shale & lime	2645
shale & lime	2704
lime	2720
lime	2795
lime	2860
lime	2900
lime	2925
lime	2958
lime	3020
lime	3120
lime	3173
lime	3240
lime	3315
lime	3370
Cherty conglom.	3389
T.D.	3433

Tops - Derrick floor

Heebner	3014
Brown lime	3102
White lime	3115
Conglomerate	3386
Total Depth	3430

RECEIVED  
STATE GOVERNMENT DIVISION

MAR 22 1951

CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
 FILE SEC 7 T 16 S R 12 W  
 PAGE 67 LINE 4