




WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - VERNON OIL & GAS CO.  
Farm - Weber No. 1.

SEC. 7 T. 16 R. 12 W  
CS  $\frac{1}{2}$  SE NE

Total Depth. 3365'  
Comm. 12-18-43 Comp. 2-20-44  
Shot or Treated.  
Contractor. Harry Gore  
Issued. 3-18-44

County. Barton  
KANSAS



CASING:  
12  $\frac{1}{2}$ " 474' P 7" 2926' UR 3183'  
10" 818' P  
8  $\frac{1}{2}$ " 2125' UR 2445'

Elevation. \_\_\_\_\_

Production. Dry

Figures Indicate Bottom of Formations.

cellar	0-10	shale blue sft	2003	lime wh hd	3255
clay yellow sft	20	lime wh hd	2064	shale blue sft	3263
lime wh hd	45	red rock sft	2070	lime wh hd	3315
shale blue sft	140	lime wh hd	2085	shale blue sft	3320
sand wh sft	160	lime sdy gy sft	2100	lime cherty & cong.	3358
red rock	170	lime brkn lgt sft	2135	Arbuckle lime wh sft	3365
lime wh hd	175	shale blue sft	2147	Total Dept h.	
sand wh sft,	250	red rock sft	2160	HFW 205	
sdv shale blue sft	265	lime wh hd	2190	HFW 500-05	
red rock	280	shale blue sft	2195	Little wtr 1750-60	
sand wh sft	310	lime wh hd	2225	1 BW 1840-50	
red rock	320	lime brkn lgt sft	2240	1 $\frac{1}{2}$ BW 2090	
shale blue sft	325	shale gy & lime shells	2290	5 BW 2380-90	
shale brown sft	335	lime wh hd	2295	2 BW 2490-2508	
sand wh sft	345	shale blue sft	2300	HFW 3152-60	
shale blue sft	360	lime wh hd	2315	Wtr from 3358-65	
sand wh sft	370	shale blue sft	2325	Wtr filled up 400' in 4 hrs	
shale blue sft	440	lime shells & shale	2340		
iron dk hd	448	lime wh hd	2380	Tops: Anhydrite 804	
shale blue sft	463	shale & shells sft	2390	Ft. Riley 1700	
iron dk hd	466	shale blue sft	2440	Topeka 2687	
shale blk sft	474	lime wh hd	2455	Dodge 2981	
shale blue sft	495	shale blue sft	2490	Lansing 3067	
red rock sft	500	sand brkn wh	2508	Chty Cong. 3323	
sand wh sft	505	lime wh hd	2543	Arbuckle 3358	
red rock	804	shale blue sft	2550		
anhydrite lime wh hd	847	lime wh hd	2565		
red rock	1030	shale blue sft	2575		
shale blue sft	1070	lime wh hd	2585		
red rock	1120	shale blue sft	2610		
shale blue sft	1230	lime wh hd	2618		
salt gy sft	1415	shale blue sft	2663		
shale blue sft	1425	lime wh hd	2677		
salt gy sft	1455	shale blue sft	2688		
shale blue sft	1475	lime brkn wh & blue	2720		
lime wh hd	1480	shale blue sft	2725		
shale blue sft	1485	lime wh hd	2827		
lime wh hd	1490	shale blue sft	2835		
shale, shells wh &		lime wh hd	2875		
blue med	1530	shale blue sft	2880		
lime wh hd	1585	lime wh hd	2890		
shale blue sft	1600	lime sdy dk med	2970		
lime wh hd	1610	shale blk sft	2973		
lime brkn wh med	1690	lime wh hd	2977		
red rock	1700	shale blue sft	2985		
lime wh hd	1820	lime Dodge wh hd	3005		
lime wh sharp	1840	shale red sft	3010		
lime wh hd	1915	shale blue sft	3058		
shale blue sft	1918	lime wh hd	3063		
lime wh hd	1925	shale blue sft	3067		
red rock sft	1937	K.C. lime wh hd	3124		
lime wh hd	1945	shale blue sft	3127		
shale blue sft	1950	lime wh hd	3152		
lime wh hd	1960	lime wh sft	3160		
shale blue sft	1965	lime wh hd	3194		
lime wh hd	1980	shale blue sft	3198		
red rock sft	1985	lime wh hd	3215		
lime wh hd	2000	shale blue sft	3220		

PLUGGING  
FILE SEC 7 T 16 R 12 W  
COOK PAGE 109 LINE 2