

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pawnee County, Sec. 24 Twp. 21S Rge. 20 ~~20~~ (W)

Location as "NE/CNW&SW" or footage from lines NW NW NW

Lease Owner: D. R. Lauck

Lease Name: Lewis Well No. 1

Office Address: 301 So. Broadway Wichita 2 Kans

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed May 29 19 55

Application for plugging filed May 29 19 55

Application for plugging approved May 29 19 55

Plugging commenced May 29 19 55

Plugging completed May 29 19 55

Reason for abandonment of well or producing formation

dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner

Producing formation none Depth to top 4606 Bottom - Total Depth of Well 4665 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		Surface	1238	8 5/8"	1238	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

mud 4665-300'
plug 300-296'
cement 296-256'
mud 256- 35'
plug 35- 31'
cement 31- 6' bottom of cellar

6-3-55

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 - 1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Oil Cementing Co.
Address Great Bend Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John H. Knightley (employee of owner) or authorized agent of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley
Wichita Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of June, 19 55

My commission expires Sept. 14, 1955

E. Elizabeth Gay
Notary Public

PLUGGING
FILE SEC 24 T 21 R 20 W
BOOK PAGE 123 LINE 19

D. R. Lauck #1 Lewis
 Commenced: May 11, 1955
 Completed: May 29, 1955

NW NW NW Sec. 24-21-20W
 Pawnee County Kans.
 Elevation: 2090 GR.
 2093 DF
 2095 KB

Casing record: 1238' 8 5/8" cem.w/475 sacks

Drillers Log

Surface clay 30
 sand 70
 shale 120
 sand & shells 135
 lime & shale 250
 shale & shells 540
 red bed & shells 630
 red bed 655
 sand 856
 red bed & shells 860
 sand 870
 red bed & shells 1230
 Anhydrite 1260
 shale & shells 1985
 Shale & lime 2425
 Lime 2490
 Lime & shale 2680
 lime 2750
 lime & shale 2950
 shale & shells 3280
 lime & shale 3659
 lime 4087
 shale 4100
 lime 4138
 lime & shale 4225
 Conglomerate 4257
 chert 4265
 lime 4330
 lime & chert 4370
 lime 4435
 lime & chert 4478
 lime 4665

RTD 4665

	Sample	Tops	Halliburton
Anhydrite	1230	865	
Topeka	3301-1206		
Heebner	3616-1521		3614-1519
Lansing	3669-1574		3666-1571
Base K.C.	4032-1937		4029-1934
Marmaton	4041-1946		4037-1942
Cherokee	4135-2040		4132-2037
Conglom.shales	4220-2125		4216-2121
Mississippian	4257-2162		4256-2161
Kinderhook	4322-2227		4319-2224
Viola	4342-2247		4337-2242
Simpson	4557-2462		4553-2458
Arbuckle	4611-2516		4606-2511
Rotary Total depth	4665-2570		4661-2566

DST#1 (Western) 4260-4265
 weak blow 5 min.; open 15 min.
 recovered 5' mud;
 BHP 1250# in 20 min.

D & A

State of Kansas)
 County of Sedgwick) SS

I hereby certify that the above is a true and correct log of the Lewis #1 well, to the best of my knowledge and belief.

John H. Knightley
 John H. Knightley

Subscribed and sworn to before me this 2nd day of June, 1955.

Elizabeth Gay
 Notary Public

My commission expires Sept. 14, 1955

RECEIVED
 STATE CORPORATION COMMISSION

JUN 3 - 1955

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING

24-21-20W
 PAGE 123