

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 24 Twp. 21 Rge. 20 (E) W (W)
C SW NE

NORTH

		X	

Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines _____
 Lease Owner Mull Drilling Co. Inc.
 Lease Name Lipp Well No. 1
 Office Address 1625 Plaza Bldg. Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry hole.
 Date well completed 8-18-63 19__
 Application for plugging filed 8-18-63 19__
 Application for plugging approved 8-18-63 19__
 Plugging commenced 6:00 P.M. 8-18-63 19__
 Plugging completed 10:30 P.M. 8-18-63 19__
 Reason for abandonment of well or producing formation Non productive.

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Petty Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4557' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe with bottom plug put at 540' with 20 sacks cement, 2nd. plug put at 240' with 20 sacks cement, and third plug put at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1963

CONSERVATION DIVISION
Wichita, Kansas

8-28-63

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Walters Drilling Co.
Address Wichita, Kansas

STATE OF KANSAS _____, COUNTY OF SEDGWICK, ss.
Joseph O. Butts (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 19 63

Bettie H. Satter
Notary Public.

My commission expires October 16, 1965

LIPP #1

LOCATION: C SW/4 NE/4 Section 24-21S-20W DATE SPUDDED: August 6th, 1963
 Pawnee County, Kansas ROTARY COMPLETION: August 18th, 1963

OPERATOR: Mull Drilling Co., Inc. ELEVATION: 2089 GL
 2091 DF

CONTRACTOR: Walters Drilling Co. 2094 KB

SURFACE CASING: 8-5/8" @ 1230' with 550 sacks cement

OIL STRING: None

L O G

(Figures indicate bottom of formation)

Shale & Shells	0-38'
Sand & Shale	92'
Shale & Shells	645'
Sand	825'
Red Bed	935'
Shale & Shells	1203'
Anhydrite	1240'
Shale & Shells	1995'
Lime & Shale	3690'
Lime	3975'
Lime & Shale	4200'
Lime	4240'
Chat	4252'
Lime & Chert	4330'
Shale, Lime & Chert	4410'
Lime	4495'
Lime & Shale	4547'
Lime	4557'
Total Depth	4557'


RECEIVED
 STATE CORPORATION COMMISSION
 AUG 28 1963
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.


 ROBERT F. WALTERS, Partner

Subscribed and sworn to before me
 this 22nd day of August, 1963.


 Velma L. Deines, Notary Public

My commission expires January 11, 1967.

