

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-20,811-0000

LEASE NAME Steffen #2

WELL NUMBER _____

SPOT LOCATION C SE NW

SEC. 5 TWP 21s RGE. 20w(E) or (W)

COUNTY Pawnee

Date Well Completed _____

Plugging Commenced 12/23/85

Plugging Completed 1/6/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hummon Corporation

ADDRESS 400 One Main Place, Wichita, Ks. 67202

PHONE # (316) 263-8521 OPERATORS LICENSE NO. 5050

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	325'	none
				4 1/2"	3797'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
Plug job only - No pipe recovery. Plugged well with 1 hull, 50 cement, 10 gel, 2 hulls, plug, & 225 sacks cement down 4 1/2". Plug fell 230'. Capped top with 2 1/2 yards ready-mix. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 26th day of December, 19 85

Irene Hoover
Notary Public

My Commission expires:



DRILLERS LOG

No. 2 Steffen

CASING RECORD: COMPANY: Hummon Corporation DESCRIPTION:

8 5/8" @ 325' CONTRACTOR: Red Tiger Drilling Company C SE/4 NW/4
w/200 sx cement

4 1/2" @ 3,792' COMMENCED: February 18, 1981 Sec. 5-T21S-R20W
w/475 sx cement COMPLETED: February 27, 1981 Pawnee County, Kansas

TOTAL DEPTH: 4,400' ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	326	
Shale	326	770	
Sand	770	992	
Sand & Shale	992	1300	
Anhydrite	1300	1325	
Shale	1325	2170	
Shale & Lime	2170	2385	
Lime & Shale	2385	2945	
Shale & Lime	2945	3315	
Lime & Shale	3315	3945	
Lime	3945	4294	
Mississippi	4294	4400	
RTD		4400	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 6th day of March, 1981.

Joyce A. Baer
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1985

CONSERVATION DIVISION
Wichita, Kansas

