

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pawnee County. Sec. 5 Twp. 21S Rge. 20W NE/4  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
150' N of C NW/4 SW/4

Lease Owner Hummon Corporation  
Lease Name Albrecht Well No. 2

Office Address 400 One Main Place, Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) D & A

Date Well completed March 10, 1981

Application for plugging filed March 10, 1981

Application for plugging approved March 10, 1981

Plugging commenced March 10, 1981

Plugging completed March 10, 1981

Reason for abandonment of well or producing formation D & A


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,400'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	317.65'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole @ 720' w/65 sx cement

@ 360' w/35 sx cement

@ 40' w/10 sx cement, 1/2 sx hulls & plug

50-50 Pozmix, 4% Gel

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company  
1720 KSB&T Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss. contractor  
Gloria Fawcett (employee of ~~XXXXXX~~)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett

1720 KSB&T Building, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of March, 1981.

Joyce A. Baer  
Notary Public.

My commission expires \_\_\_\_\_

Notary Public.

3-19-81  
MAR 19 1981



CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS LOG

No. 2 Albrecht

CASING RECORD: 8 5/8" @ 324'  
w/225 sx cement

COMPANY: Hummon Corporation

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: March 2, 1981

D & A

COMPLETED: March 10, 1981

TOTAL DEPTH: 4,400'

DESCRIPTION: 150' N of C NW/4 SW/4  
Sec. 5-T21S-R20W  
Pawnee County, Kansas

ELEVATION: 2,157' GR

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	325	
Shale	325	760	
Sand & Shale	760	980	
Shale	980	1330	
Anhydrite	1330	1360	
Shale	1360	2040	
Lime & Shale	2040	2198	
Shale & Lime	2198	2585	
Lime & Shale	2585	3228	
Shale & Lime	3228	3540	
Lime & Shale	3540	3705	
Lime	3705	4341	
Mississippi	4341	4400	
RTD		4400	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett  
Gloria Fawcett

Subscribed and sworn to before me this 17th day of March, 1981.

Joyce A. Baer  
Notary Public



RECEIVED  
STATE CORPORATION COMMISSION

MAR 19 1981

CONSERVATION DIVISION  
Wichita, Kansas