

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-033-21636-01-00
 Spot: SESESWSE Sec/Twnshp/Rge: 26-31S-20W
300 feet from S Section Line, 1635 feet from E Section Line
 Lease Name: HAROLD Well #: 1-26H
 County: COMANCHE Total Vertical Depth: 5164 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5218		WITH 100 SX CMT
COND	20	110		WITH 11 SX CMT yards
	L1 4.5	9389		WITH 500 SX CMT
PROD	7	5570	1786	WITH 300 SX CMT
SURF	9.625	942		WITH 470 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/28/2017 8:30 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5218' WITH 100 SX CMT. PLUG AT 970' WITH 70 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 04/28/2017 9:45 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

TOP OF 4 1/2" LINER AT 5268'. SET CIBP @ 5218'. CIRCULATED 190 BBL MUD THEN SPOTTED 100 SX CMT ON TOP OF CIBP. 1ST PLUG AT 970' WITH 70 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
8597	8902		
8219	8523		
7840	8145		
7462	7767		
7083	7388		
6693	7010		
6327	6631		
6024	6253		
5570	5875		

INVOICED
 MAY 22 2017

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS C CEMENT BY ORR ENTERPRISES. TMD= 9389'

Plugged through: TBG

District: 01

5-2-17
 RECEIVED
 MAY - 2 2017
 KCC DODGE CITY

Signed [Signature]
 SA (TECHNICIAN)