

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-077-21974-01-00
Spot: N2N2N2NE **Sec/Twnshp/Rge:** 14-35S-8W
200 feet from N Section Line, 1320 feet from E Section Line
Lease Name: LIT TRUST 3508 **Well #:** 5-14H
County: HARPER **Total Vertical Depth:** 5703 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		10 SX
PROD	7	5703		340 SX
SURF	9.625	770		400 SX
T1	4.5	774		

Well Type: OIL **UIC Docket No:** _____ **Date/Time to Plug:** 04/13/2017 12:00 AM
Plug Co. License No.: 33338 **Plug Co. Name:** ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR **Company:** ORR ENTERPRISES **Phone:** (405) 429-6002

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON **WitnessType:** NONE
Date/Time Plugging Completed: 04/19/2017 5:30 PM **KCC Agent:** STEVE VANGIESON

Actual Plugging Report:

TIH WITH TUBING WITH 7" CIBP. SET BP AT 5000'. RELEASE D PLUG & PUMPED 190 BBL MUD TO LEAD HOLE, FOLLOWED BY 100 SX CLASS C CEMENT. NO STRETCH ON 7" CASING - PERFORATED 4 HOLES AT 1400'. RAN TUBING TO 1415' & SPOTTED 7 BBLs CEMENT. TAGGED CEMENT AT 1253'. PERF'D @ 897', TIH WITH TUBING TO 907', PRESSURED UP & HELD 800# PSI. SPOTTED 50 SX @ 907'. PULLED TUBING TO 300' & CIRCUALTE CASING WITH 100 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
7685	7688		
7611	7614		
7547	7550		
7481	7484		
7405	7408		
7317	7320		
7232	7235		
7068	7071		
7047	7150		
6998	7001		
6923	6926		
6873	6876		
6801	6804		
6739	6742		
6675	6678		
6575	6578		
6512	6515		
6447	6450		
6337	6340		
6272	6275		
6207	6210		
6132	6135		
6052	6055		
5972	5975		
5900	5903		
5829	5832		
5772	5775		
5468	5470		
5318	5320		
5222	5224		

-INVOICED

MAY 22 2017


JK

Remarks: ORR ENTERPRISES CLASS "C" CEMENT, COMPLIANCE DENIED TA, TMD = 7774

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

Form CP-2/3