

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-077-21968-01-00
 Spot: SESESWSE Sec/Twnshp/Rgc: 15-35S-8W
200 feet from S Section Line, 1340 feet from E Section Line
 Lease Name: BRYANT 3508 Well #: 6-10H
 County: HARPER Total Vertical Depth: 4810 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		
L1	4.5	7405		
PROD	7	5677		340 SX
SURF	9.625	780		430 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2017 12:00 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES Phone: (405) 429-5610

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
 Date/Time Plugging Completed: 04/25/2017 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET 7" CIBP AT 5200', ON TUBING. RELEASED FROM BP & CIRCULATED 190 BBLs OF MUD, FOLLOWED BY 100 SKS CEMENT. LAYED DOWN TUBING. RECOVERED 1431' 7" CASING. TIH WITH TUBING TO 1400', SPOT 50 SKS CEMENT. PULL TUBING TO 900', SPOT 50 SKS CEMENT. PULLED TUBING TO 300' & CIRCULATED CEMENT TO 0' WITH 100 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
6759	6762		
6672	6675		
6601	6604		
6547	6555		
6460	6463		
6372	6375		
6287	6290		
6222	6225		
6159	6162		
6097	6100		
5997	6000		
5945	5948		
5885	5888		
5815	5818		
5768	5771		
5697	5700		
5516	5518		
5450	5452		
5382	5384		


Remarks: ORR ENTERPRISES, CLASS C. COMPLIANCE DENIED TA. TMD = 7405

Plugged through: TBG

INVOICED
 MAY 22 2017

District: 02

Signed _____



(TECHNICIAN)

✓