

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22714-01-00
Spot: SWSWSESW Sec/Twnshp/Rge: 4-34S-4W
200 feet from S Section Line, 1550 feet from W Section Line
Lease Name: BARBARA 3404 Well #: 1-9H
County: SUMNER Total Vertical Depth: 5400 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	16	90		10 SX
	11 7	5400		380 SX
PROD	4.5	9654		0 SX
SURF	9.63	495		240 SX
TI	2.87	5298		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2017 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES Phone: (405) 429-6002

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 04/13/2017 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET 7" CIBP ON TUBING AT 5150'. RELEASED B.P. & CIRCULATED 190 BBLS OF MUD, FOLLOWED BY 100 SX CEMENT. RECOVERED & LAYED DOWN 764' OF 7" CASING. TIH WITH TUBING TO 750', SPOT 60 SX CEMENT. PULL TUBING TO 550' & SPOT 50 SX CEMENT. PULL TUBING TO 300' & CIRCUALTE CEMENT TO SURFACE WITH 100 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
9276	9546		
9020	9188		
8484	8876		
8092	8398		
7762	8042		
7336	7648		
7004	7249		
6562	6906		
6207	6452		
5810	6133		
5412	5724		

Remarks: ORR ENTERPRISES, CLASS C CEMENT. TMD = 9654

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

INVOICED
MAY 22 2017