

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-20701-00-02
Spot: SENW Sec/Twnship/Rge: 3-33S-41W
3300 feet from S Section Line, 3300 feet from E Section Line
Lense Name: BERRYMAN RICHFIELD UNIT Well #: 11-2
County: MORTON Total Vertical Depth: 5125 feet

Operator License No.: 34832
Op Name: SCOUT ENERGY MANAGEMENT LLC
Address: 4901 LBJ FREEWAY SUITE 300
DALLAS, TX 75244

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5134	1570	WITH 350 SX CMT
SURF	8.625	1467		WITH 550 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2016 4:30 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: TAG TOP @ 3735' & SPOT 80 SX CMT ON TOP. PLUG AT 1500' WITH 50 SX CMT. PLUG AT 570' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 04/13/2017 10:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

4/11/17: TAG TOP OF FISH @ 3735' & SPOT 80 SX CMT WITH 200# HULLS. WOC & ATTEMPT TO TAG. NO TAG. SPOT ANOTHER 80 SX CMT WITH 200# HULLS AT 3735'. 4/12/17: TAG TOC @ 3175'. CUT & PULL CASING. 1ST PLUG AT 1500' WITH 50 SX CMT. NO CIRCULATION. SHUT DOWN & TAG. 4/13/17: TAG TOC @ 1387'. 2ND PLUG AT 570' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Top	Bot	Thru	Comments
5037	5042	CSG	

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

INVOICED
MAY 22 2017

District: 01

Signed _____



(TECHNICIAN)

RECEIVED
APR 18 2017
KCC DODGE CITY

514

Form CP-2/3