

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-21182-00-00
Spot: NENESE Sec/Twnshp/Rge: 15-18S-18W
2297 feet from S Section Line, 343 feet from E Section Line
Lease Name: O JONES Well #: 1
County: RUSH Total Vertical Depth: 3809 feet

Operator License No.: 33372
Op Name: TAOS RESOURCES OPERATING COMP
Address: 1455 W LOOP S SUITE 600
HOUSTON, TX 77027

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3659		WITH 2 SX CMT
PROD	5.5	3809	1230	WITH 1003 SX CMT
SURF	8.625	1195		WITH 425 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/17/2017 9:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: RAY DOROTHY Company: TAOS RESOURCES Phone: (308) 340-4029

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS & 2 SX CMT. PLUG AT 1220' WITH 50 SX CMT. PLUG AT 660' WITH 40 SX CMT. PLUG AT 250' WITH 50 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/18/2017 12:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3659' WITH 2 SX CMT. 1ST PLUG AT 1220' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 40 SX CMT. 3RD PLUG AT 250' WITH 50 SX CMT TO SURFACE. PULL CASING OUT OF HOLE & TOP OFF WITH 10 SX CMT. HOLE STANDING FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
3804	3809	CSG	

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

INVOICED

Plugged through: CSG

MAY 22 2017

District: 01

4-28-17
RECEIVED
APR 28 2017
KCC DODGE CITY

Signed

[Signature]
5A

(TECHNICIAN)