

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-20844-00-00
Spot: SWNE Sec/Twnshp/Rgc: 35-27S-19W
3295 feet from S Section Line, 2246 feet from E Section Line
Lease Name: ASHLEY Well #: 2
County: KIOWA Total Vertical Depth: 4847 feet

Operator License No.: 5118
Op Name: TGT PETROLEUM CORPORATION
Address: 7570 W 21ST ST N BLDG 1046A
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4700		WITH 2 SX CMT
PROD	5.5	4844	1676	WITH 250 SX CMT
SURF	8.625	418		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/20/2017 3:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: SPENCER SIROKY Company: FOSSIL DRILLING Phone: (316) 773-2266

Proposed Plugging Method: CIBP @ 4700' WITH 2 SX CMT. PLUG AT 1260' WITH 12 SX GEL & 50 SX CMT. PLUG AT 430' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/20/2017 6:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4700' WITH 2 SX CMT. 1ST PLUG AT 1268' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4780	4784		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

INVOICED

MAY 22 2017

District: 01

Signed _____

SR
(TECHNICIAN)

RECEIVED
APR 21 2017
KCC DODGE CITY