

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-21633-00-00
Spot: SENWSESW Sec/Twnshp/Rge: 3-32S-12E
819 feet from S Section Line, 3556 feet from E Section Line
Lease Name: MUSTOE Well #: 2
County: CHAUTAUQUA Total Vertical Depth: 430 feet

Operator License No.: 32967
Op Name: WOLFE, LESLIE
Address: 208 STEPHENS ST
PERU, KS 67360

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	420		40 SX
SURF	8.625	40		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/25/2017 12:00 AM
Plug Co. License No.: 32967 Plug Co. Name: WOLFE, LESLIE
Proposal Rcvd. from: LESLIE WOLFE Company: _____ Phone: (620) 404-0146

Proposed
Plugging
Method:

Pull to tubing to bottom, pump 2 barrels of gel, layer 10 sacks of cement, pull tubing to 275ft, fill surface with cement.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/25/2017 10:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Perfs:

Ran 2-3/8" tubing to TD. Pumped 1 sack of gel at TD then pumped 9 sacks of portland cement. Pulled tubing up to 275' and circulated cement to surface. Pulled all but 40' of tubing and circulated cement to surface again. Pulled remaining tubing and topped off. 31 sacks of cement used.

RECEIVED
KCC DIST # 3
MAY 10 2017
CHANUTE, KS

RH

INVOICED
MAY 22 2017

Remarks: THIS WELL IS LISTED ON A COMPLIANCE AGREEMENT

Plugged through: TBG

District: 03

Signed

Russell Hine

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 15 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3