

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-189-22525-00-00  
 Spot: W2SESWSE Sec/Twnshp/Rge: 3-34S-37W  
331 feet from S Section Line, 1781 feet from E Section Line  
 Lease Name: MAURINE Well #: 3-1  
 County: STEVENS Total Vertical Depth: 6850 feet

Operator License No.: 32864  
 Op Name: XTO ENERGY INC.  
 Address: 210 PARK AVE STE 2350  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6250		WITH 10 SX CMT
CIBP		6620		
PROD	4.5	6844	1768	WITH 510 SX CMT
SURF	8.625	1700		WITH 480 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/18/2017 10:00 AM  
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
 Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Set CIBP @ 6250' & cap w/ 10 sx cement. Pull up hole to 3250, spot 20 sx cmt from 3250' - 3150' to cover DV tool @ 3200'. Pull up hole to +/- 2000' and cut and pull free pipe. Spot 50 sx Class "C" cmt from 2000' to 1800'. Tag to ensure TOC is 1800' or higher. POH to 650', spot 50 sxs cmt from 650' - 550' to cover the base of treatable water @ 600'. POH to 64', spot 20 sxs cmt from 64' to 4' below surface. Cut and cap well. Weld on identification plate.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
 Date/Time Plugging Completed: 04/18/2017 2:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 6250' WITH 10 SX CMT. 1ST PLUG AT 3250' WITH 20 SX CMT OVER DV TOOL. 2ND PLUG AT 1768' WITH 50 SX CMT. 3RD PLUG AT 648' WITH 50 SX CMT. 4TH PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6663	6673		
6312	6324		

INVOICED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED COMMON CEMENT BY ORR ENTERPRISES MAY 22 2017

Plugged through: TBG

District: 01

Signed [Signature]  
 (TECHNICIAN)

RECEIVED  
 APR 25 2017  
 KCC DODGE CITY [Signature]