

1 070998

10-28

48R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,792-0000

C NE SEC. 16 T 21 S, R 20 WXX

3960 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Tammen Well # 1-16

Operator: Benson Mineral Group, Inc.
Name & Address 1560 Broadway, Suite 1900
Denver, CO 80202

County Pawnee 78.00

Well Total Depth 2400 feet

Conductor Pipe: Size feet

Surface Casing: Size 7" feet 975

Abandoned Oil Well Gas Well X Input Well SHD Well O&A

Other well as hereinafter indicated

Plugging Contractor Benson Mineral Group, Inc. License Number 5817

Address 1560 Broadway, Suite 1900, Denver, CO 80202

Company to plug at: Hour: 2 p.m. Day: 28 Month: 10 Year: 19 91

Plugging proposal received from Murray Brooks

(company name) Benson Mineral Group, Inc. (phone) 303-863-3500

were: 4 1/2" at 2393' w/350 sx cement, PBSD 2373', Perfs at 2242-52, 2188-98'

1st plug pump 300 lbs. hulls and 50 sx cement,

2nd plug perforate at 800' and pump 115 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:30 p.m. Day: 28 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls and 50 sx cement, displaced to 1300' to 800#,

2nd plug perforated at 800' and pumped 115 sx cement, cement circulated to surface.

RECEIVED STATE CORPORATION COMMISSION

11-18-91

NOV 18 1991

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 11-25-91

INV. NO. 33860

Signed Dan Goodrow (TECHNICIAN)