

To: 1 052079
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-145-21,442-0000
C SW, SEC. 15, T 21 S, R 20 WXX
1320 feet from S section line
1320 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4629
Operator: Brito Oil Company, Inc.
Name:
Address: 120 S. Market, Ste. 300
Wichita, KS 67202

Lease Name Scott Well # 1-15
County Pawnee 75.92
Well Total Depth 2336 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 359

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor: Duke Drilling Co., Inc. License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 31 Month: 10 Year: 19 96

Plugging proposal received from Rich Wheeler
(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

- Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1248'
- 1st plug at 1260' with 50 sx cement,
 - 2nd plug at 390' with 50 sx cement,
 - 3rd plug at 40-0' with 10 sx cement,
 - 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 31 Month: 10 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 1260' with 50 sx cement,
2nd plug at 390' with 50 sx cement,
3rd plug at 40-0' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

11-4-96

RECEIVED
NOV 11 1996
4 11:52

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 11-5-96
INV. NO. 46909

Signed Richard W. Lacey (TECHNICIAN)

FOR KGS USE:

EFFECTIVE DATE: 10-17-96

DISTRICT # 1
SEAT Yes No

State of Kansas

15-145-21,442-0000

NOTICE OF INTENTION TO DRILL

FORM G-1 7/97
FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10-21-96
month day year

Spot C SW Sec 15 Twp 21 S. 20W East
X West

OPERATOR: License # 4629
Name: Brito Oil Company, Inc.
Address: 120 S. Market, Suite 300
City/State/Zip: Wichita, KS 67202
Contact Person: Raul F. Brito
Phone: 316 263-8787
Fax: 316 262-4504
CONTRACTOR: License #: 5929
Name: Duke Drilling Company, Inc.

1320 FSL feet from South / North line of Section
1320 FWL feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Pawnee
Lease Name: Scott Well #: 1-15
Field Name: Bryant

Is this a Protected/Spaced Field? yes X no
Target Formation(s): Krider

Nearest Lease or unit boundary: 1320'

Ground Surface Elevation: Est. 2100 feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 180'

Depth to bottom of usable water: 300'

Surface Pipe by Alternates: X 1 2

Length of Surface Pipe Planned to be set: 350'

Length of Conductor pipe required: none

Projected Total Depth: 2350'

Formation at Total Depth: Krider

Water Source for Drilling Operations:

well X farm pond X other

DWR Permit #: _____

Will Cores be Taken?: yes X no

If yes, proposed zone: _____

320' Alt. I. Req.

Well Drilled For: Well Class: Type Equipment:

X Oil ... Enh Rec ... Infield X Mud Rotary
X Gas ... Storage X Pool Ext. ... Air Rotary
... OAWD ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
... Other

If OAWD: old well information as follows:

Operator: _____

Well Name: _____

Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes X no

If yes, true vertical depth: _____

Bottom Hole Location: _____

AFFIDAVIT

Exp. 4/7/97

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well STATE CORPORATION REGISTRATION NO. 101, et. seq.

RECEIVED
STATE CORPORATION REGISTRATION NO. 101, et. seq.

Pusher Rich
SPUD DATE 10-28-96 INIT. KS
LENGTH SURFACE PLANNED 350'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPES @ 359 CONDUCTOR
ANHYDRITE T- B-1248 ELEVATION

TD 2336 FORMATION Krider
RAN PIPE @ DV TOOL ALT II DONE
Arbuckle Plug @ Ft. W/ SX Y N SX
Hng./Council @ Ft. W/ SX
Anhydrite Base @ 1260 Ft. W/ SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ 390 Ft. W/ SX
Bottom Surface @ Ft. W/ SX
40' Plug @ 40-0 Ft. W/ 10 SX
RAT HOLE CIRC/W SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN SD DATE 10/31-96
TYPE OF CEMENT 61Y 6% by Allied
STARTING TIME 12:30 (AM/PM) DATE 10-31-96
COMPLETION TIME 3:30 (AM/PM) DATE 10-31-96
CEMENT COMPANY Orders by S-D
1 CREW witnessed