

1 070996

10-29

479

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,798-0000  
C NE , SEC. 14 , T 21 S, R 20 W/X  
3960 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817  
Operator: Benson Mineral Group, Inc.  
Name & Address 1560 Broadway, Suite 1900  
Denver, CO 80202

Lease Name Sales Well # 2-14  
County Pawnee 76.63  
Well Total Depth 2358 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 7" feet 955

Abandoned Oil Well Gas Well  Input Well SWD Well D&A  
Other well as hereinafter indicated

Plugging Contractor Benson Mineral Group, Inc. License Number 5817  
Address 1560 Broadway, Suite 1900, Denver, CO 80202

Company to plug at: Hour: 10 a.m. Day: 28 Month: 10 Year: 19 91

Plugging proposal received from Murray Brooks

(company name) Benson Mineral Group, Inc. (phone) 803-863-3500

were: 4 1/2" at 2357' w/220 sx cement, PBSD 2348', Perfs at 2193-2202'

1st plug pump 2 sx hulls and 20 sx cement on bottom,  
2nd plug pump 300 lbs. hulls and 250 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 11 a.m. Day: 29 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls and 50 sx cement, displaced to  
1200' at 1200#,

2nd plug perforated at 900', would not take, perforated at 500', would not take, pressured  
down annulus, held at 1500#.

Ran tubing to 850' and circulated to 0' with 70' sx cement.

Cemented near surface.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
DATE 11-25-91  
INV. NO. 33859

Signed Dan Goodrow  
(TECHNICIAN) 11-18-91

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 18 1991  
CON DIVISION  
Wichita Kansas