

1060156

TO: STATE CORPORATION COMMISSION

4-20

API NUMBER 15-083-20,975-0000  
NW/4 SEC. 23, T 21 S, R 21 W

CONSERVATION DIVISION - PLUGGING SECTION 4950 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4950 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME FIVE STAR WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY HODGEMAN 139.98

OPERATOR LICENSE # 5030

WELL TOTAL DEPTH 4307 FEET

OPERATOR: VESS OIL CORPORATION PRODUCTION CSG: SIZE 5 1/2" @ 4303' WITH 150 SX

NAME AND ADDRESS 8100 E 22ND ST N BLDG 300 SURFACE CASING: SIZE 8 5/8" @ 1280' WITH 475 SX

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 10:20 AM DAY: 20 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: OPEN HOLE

1ST PLUG SANDED TO 4250' AND 4 SX CEMENT.

2ND PLUG AT 1300' WITH 50 SX CEMENT AND 200# HULLS.

3RD PLUG AT 600' WITH 100 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 20 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SANDED TO 4250' AND 4 SX CEMENT.

2ND PLUG AT 1300' WITH 50 SX CEMENT AND 200# HULLS.

3RD PLUG AT 600' WITH 100 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2200' OF 5 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED  
IF YOU OBSERVE THIS PLUGGING.

STATE CORPORATION COMMISSION  
APR 28 1999 SIGNED

Michael J Maier  
(TECHNICIAN) FORM CP-2/3

DATE 4-30-99

INV. NO. 60912

4-28-99  
CONSERVATION DIVISION  
Wichita, Kansas