

12-7 15.083-10037-0000

To: 1 070767
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 4/14/63
C SE NE, SEC. 16, T 21 S, R 21 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229
Operator: Phillips Petroleum Company
Name & Address Route 3, Box 20-A
Great Bend, KS 67530

Lease Name Mooney AB Well # 1
County Hodgeman 142.25
Well Total Depth 4377 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Phillips Petroleum Company License Number 5229

Address Route 3, Box 20-A, Great Bend, KS 67530

Company to plug at: Hour: 12:30 p.m. Day: 7 Month: 12 Year: 19 89

Plugging proposal received from Fred Smith

(company name) Phillips Petroleum Company (phone) 316-793-8421

were: 5 1/2" at 4375' PBD 4326' Perfs at 4311-4323.5'

1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,

2nd plug perforate at 690', pump 150 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 p.m. Day: 7 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4230' and dumped 5 sx cement on top of sand through bailer,

2nd plug pressured backside to 800#, would not take. Shot casing at 695', pumped 150 sx cement.

Maximum pressure 800 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

(I, Richard W. Lacey, hereby observe this plugging.)

DATE DEC 14 1989

Signed Dan Andrew
(TECHNICIAN)

NO. 26805
12-7

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1989 12-12-89

CONSERVATION DIVISION