

To: 1 060027
STATE CORPORATION COMMISSION

4-1

API NUMBER 15-083-21,221-0000

Wichita State Office Bldg. - PLUGGING SECTION 20' W
130 S. Market, Room 2078
Wichita, KS 67202

of C S/2 SEC. 16, T 21 S, R 22 W/EX

1320 feet from S section line

2660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7146

Lease Name Wieland Well # 2

Operator: Cheyenne Oil Service, Inc.

County Hodgeman

Name: P.O. Box 384

Well Total Depth 4463 feet

Address: Ness City, KS 67560

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 473

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co., Inc. License Number

Address

Company to plug at: Hour: 10:15 a.m. Day: 1 Month: 4 Year: 1997

Plugging proposal received from Morris Smith

(company name) Allied Cementing (phone)

Notes: 4 1/2" at 4462' w/110 sx cement, couldn't get below 844' with tubing, tubing & rods still in hole, casing may be collapsed.
1st plug run tubing to 844' and fill with cement, circulating.

RECEIVED
KANSAS CORP COM
1997 APR -4 A 11:52 AM

4-4-97

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 1 Month: 4 Year: 1997

ACTUAL PLUGGING REPORT Perforated at 650', ran tubing to 844', mixed cement and hulls and

fill water circulated out backside. Shut down, pulled tubing.

Pumped 80 sx cement down casing and 80 sx cement down backside.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

Signed Michael J. Maier (TECHNICIAN)

DATE 4-1-97

INV. NO. 47863. 47863