

1 080036

8-29 15-083-10044-0000

364 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 8/19/60

C NW NW, SEC. 18, T 21 S, R 22 W/R

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6593

Lease Name Cossman Well # 2

Operator: Coastal Oil & Gas Corporation

County Hodgeman

Name & Address 211 North Robinson, Suite 1700

Well Total Depth 4451 feet

Oklahoma City, OK 73102

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Coastal Oil & Gas Corporation License Number 6593

Address 211 North Robinson, Suite 1700, Oklahoma City, OK 73102

Company to plug at: Hour: 10 a.m. Day: 29 Month: 8 Year: 19 88

Plugging proposal received from C. Brad Crouch

(company name) Coastal Oil & Gas Corporation (phone) 405-239-7031

were: 5 1/2" at 4446' PBTD 4408' Perfs at 4362-4380'

1st plug pump 5 sx hulls and 185 sx econolight cement,

2nd plug pump 100 sx cement down annulus.

RECEIVED
STATE CORPORATION COMMISSION

SEP - 2 1988

9-2-88

Plugging Proposal Received by Paul A. Luthi
Wichita, Kansas (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 8 p.m. Day: 29 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 10-11:48 a.m., wait on Halliburton, 11:48-12:28 p.m., rig up cements, 12:28 p.m. - began pumping to fill hole, rate at 1/4 bbl/min/500 psi (no hulls were run due to rate), cement in at 12:45 p.m. 1/2 bbl/500, 10 min. 1/2 bbl/550, 1:10 1/2 bbl/1000 psi, 2 p.m. 1/2 bbl at 600 psi, 3:30 p.m. had 150 sx-shut in with 200 psi, 20" 0 psi (kick in pump and immed. pressure), 3:55 pump cement, 4 p.m. complete cement-185 sx,-shut in w/200 psi. Shut in one hour. Pumped 20 sx cement to fill 8 5/8".

Remarks: Used econolite by Halliburton. No casing recovery. CASING 3q. UP hole + DU tool - Cmt. W.A.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and/or XXXXXX) observe this plugging.

DATE 9-9-88

Signed Mike Spain
(TECHNICIAN)

INV. NO. 22192

8-29

50