

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-20873-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 18-21S-22W  
3680 feet from S Section Line, 4265 feet from E Section Line  
Lease/Unit Name: WIELAND Well Number: 2  
County: HODGEMAN Total Vertical Depth: 1150 feet

Operator License No.: 32568  
Op Name: CAPCO RESOURCE CORPORATION  
Address: 2922 CHAPMAN AVE - SUITE 202  
ORANGE, CA 92869

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 367 360 SX CMT  
Production: Size 5.5 feet: 1109 235 SX CMT \$ 37.38  
Liner: Size feet:

Well Type: SWD UIC Docket No: D20290.0 Date/Time to Plug: 11/22/2000 12:00 AM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: RONALD S. SCHREADER Company: Phone: (316) 263-0898

Proposed Plugging Method: PUMP DOWN EXISTING CASING WITH 300# HULLS & 100 SX OF 60/40 POZ WITH 6% GEL CEMENT. PRESSURE TEST 8 5/8" X 5 1/2" X 4 1/2". CEMENT BACK SIDE AS NECESSARY.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/22/2000 1:30 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

MIXED 200 # HULLS WITH FIRST OF CEMENT. MIXED TOTAL OF 90 SXS CEMENT AND PRESSURED TO 600# AND SHUT IN WITH 400#. TIED ONTO BACKSIDE AND PRESSURE RIGHT UP TO 500#.

INVOICE  
DATE 03-06-2001  
INV. NO. 2001010220  
RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 24 2001

CONSERVATION DIVISION  
WICHITA, KS

2-24-01

Remarks:

Plugged through: CSG

District: 01

Signed

Michael Maier  
(TECHNICIAN)