

1051914

3-28

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 083-20,849-0000
NE NE NW, SEC. 17, T 21 S, R 22 W/EX
4950 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5339
Operator: Bergman Oil Co. L.C.
Name:
Address 520 Union Center Bldg.
Wichita, KS 67202

Lease Name Antrim Well # 1
County Hodgeman
Well Total Depth 4370 142.03 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Bergman Oil Co., L.C. License Number 5339
Address 520 Union Center Bldg., Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 28 Month: 3 Year: 19 95

Plugging proposal received from Vernon Flughoft

(company name) Bergman Oil Co. (phone) 316-562-3420

Work: 5 1/2" at 4366' w/100 sx cement, Open hole 4366-70', Well was squeezed at 830' w/150 sx cmt. 2 7/8" tubing fish at 3500'.

1st plug run tubing to 3500', spot 10 sx gel and 35 sx cement,

2nd plug pull tubing to 1380' and circulate cement,

3rd plug pump 125 sx cement down 8 5/8" X 5 1/2" annulus,

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:15 p.m. Day: 28 Month: 3 Year: 1995

ACTUAL PLUGGING REPORT 1st plug ran tubing to 3500' and spotted 10 sx gel and 35 sx cement with 200 lbs. hulls mixed in,

2nd plug pulled tubing to 1390' and circulated cement to surface,

3rd plug pumped down 8 5/8" X 5 1/2" annulus with 150 sx cement. 3-30-95

Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

INVOICED (if additional description is necessary, use BACK of this form.)
I (did / did not) observe this plugging

DATE 4-7-95

INV. NO. 42516

RECEIVED STATE CORPORATION COMMISSION
APR 10 1995
WICHITA, KANSAS

Richard W. Lacey (TECHNICIAN)