

To: 1 070426
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-18-87
API NUMBER 15- NA 15-083-10208-0000
SW NE, SEC. 8, T 21 S, R 22 W/E
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address 110 North Market, Suite 205
Wichita, KS 67202

Lease Name Tricker Well # 2
County Hodgeman 142.58
Well Total Depth 4387 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123
Address 110 North Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 18 Month: 9 Year: 19 87

Plugging proposal received from Danny Biggs

(company name) Pickrell Drilling Company, Inc. (phone) 316-793-5742

were: 5 1/2" at 4386' PRTD 4310' (CIBP) Perfs 4240-46, 4337-47' -below CIBP

1st plug pump 50 lbs. hulls and 120 sx ATL cement, displace 5 1/2" wiper plug to 835',

2nd plug perforate 5 1/2" at 777-80', pump 50 sx common cement, 75 sx 60/40 Pozmix cement.

RECEIVED
STATE CORPORATION COMMISSION 9-23-87

SEP 23 1987 Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Wichita, Kansas

Operations Completed: Hour: 11:30 a.m. Day: 18 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 50 lbs. hulls and 120 sx ATL cement, displaced

5 1/2" wiper plug to 835' (this was done on 9/16/87),

2nd plug perforated 5 1/2" at 777-80', pumped 50 sx common cement, 75 sx 60/40 Pozmix cement.

Maximum pressure 500 psi and shut in 200 psi.

Used ATL cement on 9/16/87.

Remarks: Used 60/40 Pozmix and common cement by Allied. No recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-24-87

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 18247
09-18 OCT 29 1987