

Orig-State Corp. Comm
B.A. Conner-9th Floor Price Tower
STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

Mary Crump-Okla City
WELL PLUGGING RECORD
K.A.R.-82-3-117

15-083-10016-0001
Well File
API NUMBER 15-083-Prior
to 1967
LEASE NAME Robinson-Waters
WELL NUMBER SO1
SPOT LOCATION NW NW
SEC. 15 TWP. 21S RGE. 21 (E) or (W)
COUNTY Hodgeman
Date Well Completed June 1964
Plugging Commenced 6-28-84
Plugging Completed 6-28-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Phillips Petroleum Company
ADDRESS Box 287, Great Bend, Kansas 67530
PHONE # (816) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Water Supply
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Cedar Hills Depth to top 860 bottom 890 T.D. PB 1195'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation Surface	Content	From	To	Size	Put in	Pulled out
Production	Water	0'	1302'	8 5/8"	1302'	-0-
	Oil & Wtr	0'	4317'	5 1/2"	2197'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. MIRU Hembree WSU & pull 2 3/8" OD Fibgls tbq. Rel WSU. MIRU B-J to 8 5/8" OD csg and plug as follows: Pmpd 1 sk hulls, mix 330 sx 50-50 Pozmix w/4% gel, & 3% CaCl @ 500#. SIP - 150#. Rel B-J. State Rep Richard Lacey on location.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor B-J Cementing License No. RECEIVED
Address Great Bend, Kansas 67530 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

Kaare A. Westby, AGENT

~~XXXXXXXXXX~~ of operator) or Wichita, Kansas

~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the ~~log~~ of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Kaare Westby
Kaare A. Westby, Agent
(Address) Box 287, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 11th day of July, 1984

Velma L. Mog
Notary Public
Velma L. Mog

My Commission expires: February 15, 1988

NOTARY DRILLING LOG

15-083-10016-0000

Operator: Beardmore Drilling Company
#1 ROBISON-WATERS
NW NW Sec. 15-218-21W
Hodgeman County, Kansas

Contractor: Rains & Williamson
Oil Co.

Commenced: 5-26-64
Completed: 6-6-64

Remarks: Set 8-5/8" surface casing at 1302' with 600 sacks common cement. Set 4317' 5-1/2" casing with 75 sacks common cement.

FORMATIONS

Surface Clay	85'
Clay & Shale	200'
Shale	490'
Shale & Red Bed	639'
Anhydrite	651'
Shale & Red Bed	740'
D Sand	920'
Shale & Shells	1030'
Shale & Red Bed	1297'
Anhydrite	1335'
Shale & Shells	2045'
Shale & Lime	2125'
Lime & Shale	2905'
Shale & Lime	3525'
Lime & Shale	4180'
Lime	4194'
Lime & Shale	4323'
Rotary Total Depth	4323'

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 8th day of June, 1964.

My Commission Expires:
January 8, 1968

Shirley Keck
Shirley Keck, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1964
CONSERVATION DIVISION
Wichita, Kansas