

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 14 Twp. 21S Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines 150' E. of Cen. NE NE

Lease Owner Birmingham-Bartlett Drilling Co.

Lease Name BLOUNT Well No. 1

Office Address 300 Kaufman Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 24, 19 67

Application for plugging filed (verbally) March 24, 19 67

Application for plugging approved (verbally) March 24, 19 67

Plugging commenced March 24, 19 67

Plugging completed March 24, 19 67

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eves

Producing formation Depth to top Bottom Total Depth of Well 4339 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	270'	8-5/8"	270'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug set at 700' with 30 sacks cement.
Center plug set at 325' with 30 sacks cement.
Top plug set at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Birmingham-Bartlett Drilling Co.
Address 300 Kaufman Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK
Richard Hindery, Partner of Birmingham-Bartlett Drilling Co., owner, operator, & contractor
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BIRMINGHAM-BARTLETT DRILLING CO.

(Signature) By Richard Hindery Partner
300 Kaufman Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of March, 19 67.

My commission expires October 2, 1970.

Beverly Larson
Beverly Larson Notary Public.

BLOUNT NO. 1 WELL

LOCATION: 150' east of center of NE/4 NE/4
Section 14-21S-21W
Hodgeman County, Kansas

SPUDED: 3-13-67
COMPLETED: 3-24-67

OWNER, OPERATOR,
and CONTRACTOR: Birmingham-Bartlett Drilling Co.
300 Kaufman Building
Wichita, Kansas 67202

SURFACE CASING: 8-5/8" casing cemented at 270'
with 185 sacks cement.

OIL STRING: None set. Dry hole.
Plugged 3-24-67.

RECORDED
STATE CORPORATION COMMISSION
MAR 28 1967
CONSERVATION DIVISION
Wichita, Kansas

LOG

(Figures indicate bottom of formation)

0 -	35	Shale and clay
	75	Sand
	200	Shale and shells
	285	Shale
	604	Shale and sand
	618	Blaine anhydrite
	705	Shale
	895	Sand
	1265	Red bed and shale
	1296	Anhydrite
	1530	Shale and red bed
	1890	Shale and shells
	2420	Lime and shale
	2515	Lime
	3841	Lime and shale
	4108	Lime
	4200	Lime and shale
	4275	Lime
	4282	Lime and chert
	4339	Lime
	4339	Rotary total depth

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the BLOUNT NO. 1 WELL as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By

Richard Hindery, Partner

Subscribed and sworn to before me
this 27th day of March, 1967.

Beverly Larson

Beverly Larson, Notary Public
My commission expires October 2, 1970.