

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Hodgeman SEC. 8 TWP. 21S RGE. 22 NE/W  
Location as in quarters or footage from lines:

C E/2 NE/4 SW/4


Locate Well  
correctly on above  
Section Platt.

Lease Owner W. C. Stewart

Lease Name Burns Well No. 1-8

Office Address 510 Texas Commerce Bank Building, Amarillo Texas 79109

Character of Well (Completed as Oil, Gas or Dry Hole): Dry

Date Well Completed October 11, 1981

Application for plugging filed October 11, 1981

Plugging commenced 6:00 PM October 11, 1981

Plugging completed 7:30 October 11, 1981

Reason for abandonment of well or producing formation

Dry

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant, Belphre, Kans

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4430'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Shale &amp; Shells</u>		<u>0</u>	<u>292</u>	<u>8 5/8</u>	<u>292</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Fill Hole Cement 50/50 Poz 4% gel 3% CC

Spot 70 sacks @ 780'

40 sacks @ 270'

Solid Briege in 8 5/8" @ 40'

10 Sacks to surface

5 sacks in Rat Hole

Hole plugged @ 7:30PM 10-11-81

Sun Cementing State Pluggor Steve Durrant

Belphre, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 14 1981  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bergman Drilling Inc. 10-14-81

520 Union Cneter, Wichita, Knasas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Harold I. Bergman (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature)

Harold I. Bergman  
(Address)  
520 Union Center, Wichita,

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 81

Alma A. Neises  
Notary Public.

My Commission expires: May 31, 1982

BERGMAN DRILLING, INC.

DRILLERS LOG

Re: Burns # 1-8  
C E/2 NE/4 SW/4 Section 8-21S-22W  
Hodgeman County, Kansas

Elevation: 2246KB

OPERATOR: W. C. Stewart

CONTRACTOR: Bergman Drilling, Inc.

COMMENCED: September 29, 1981

COMPLETED: October 11, 1981


TOTAL DEPTH: 4430' Set 8 5/8" @ 292' w/160 sx.

0	67	Shale & Shells
67	70	Pyrite
70	295	Shale & Shells
295	1106	Shale & Shells - Red Bed
1106	1411	Shale & Shells
1411	1446	Anhydrite
1446	1650	Shale & Red Bed
1650	2045	Lime & Shale
2045	2495	Lime & Shale
2495	2720	Lime & Shale
2720	2870	Lime & Shale
2870	3094	Lime & Shale
3094	3200	Lime & Shale
3200	3340	Lime & Shale
3340	3537	Lime & Shale
3537	3730	Lime & Shale
3730	3820	Lime & Shale
3820	3918	Lime & Shale
3918	3988	Lime & Shale
3988	4144	Lime & Shale
4144	4187	Lime & Shale
4187	4312	Lime & Shale
4312	4330	Lime & Shale
4330	4360	Lime & Shale
4360	4384	Lime & Shale
4384	4388	Misc Chert
4388	4430	Misc.
4430		RTD

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 14 1981  
CONSERVATION DIVISION  
Wichita, Kansas

D & A

We certify that the above and foregoing to be true and correct copy of the Drillers log on the # 1-8 Burns, located in Hodgeman County, Kansas as revealed by the records of Bergman Drilling, Inc.

  
Harold I. Bergman

Subscribed and sworn to before me this 13th day of October, 1981

  
Alma A. Neises, Notary Public

My commission expires May 31, 1982